

City of Portland
 Ionia County, Michigan
 2007-2008 Street Inventory
 updated 9-29-2009
 Ranking Criteria: Priority - Top 20

Priority	Street Name	From	To	Length	Type	Width (ft)	Walks	Traffic Volume	Sanitary Condition	Water	ACT 51 Classification	PASER	Reconstructed	Action	Recommended Cross Section or Fix	Estimated Cost
1	Grape St	W Grand River	Ionia Rd	2627	Asphalt	31'	Yes	Moderate (school traffic)	Poor	6" Cast; 5 breaks	Local	1	Gr River to Center 1984	Reconstruct with water and sewer	bb 31'	\$ 1,540,000
2	Cutler Road	Charlotte Hwy	Grand River Ave							12" Ductile		1		Reconstruct		\$ 852,000
3	Divine Hwy N	E Grand River	City Limit	5540	Asphalt	22'	Yes	High	Poor	10" ductile to Maynard	Major	1	N of Lkg Glass 1982	Needs Total Reconstruction/Poor Intersection. A Cap on Road could gain another 10 years.	bb31'	\$ 2,870,000
4	Church St	Grand River	Detroit St	1302	Asphalt	40'	Yes	Moderate	Poor	4" Cast	Local	1	GR to Center 1984	Reconstruct w/water and sewer	bb 31'	\$ 729,000
5	Grand River W		Grove St	2262	Asphalt over Crushed Concret	43'	Yes	Moderate		10" Ductile	Major	2		Very Poor Condition Reconstruct Required	bb43'	\$ 679,000
6	Center St	Quarterline	Grape St	1135	Asphalt	33'-40'	Yes	High (School Traffic)	Poor	6" Cast; 1 break near West	Local	4	1984	Structural Improvements Crack Sealing water and sewer	bb 31'	\$ 636,000
7	Barley Ave	Kent	Storz Ave	682	Asphalt	34'	Yes	Moderate	Poor	6" Cast; 2 breaks	Local	3	1984	Structural Improvements Required, water/sewer	bb 31'	\$ 382,000
8	Knox Ave	Kent	Storz Ave	682	Asphalt	34'	Yes	Medium during AM School Traffic	Poor	6" Cast; 2 breaks	Local	3	1984	Structural Improvements, water/sewer	bb 31'	\$ 382,000
9	Empire	Elbro	Quarterline	157	Asphalt	34'	Yes	Low	Poor	.25"	Local	4		Structural Improvements Required, water/sewer	bb31'	\$ 88,000
10	Kearney	Bridge St	James N	432	Gravel	Should be 31'	No	Very Low		8" Ductile for 1/3 ; needs 8" rest of way; 2 breaks near Academy	Local	1		Total Reconstruction, water	bb 31'	\$ 163,000
11	Church St	Detroit	Lyons St	1045	Asphalt	31'	Yes	Low		8" Ductile	Local	2		Reconstruct Required	bb 31'	\$ 314,000
12	Maynard Rd	Divine Hwy	City Limit	3480	Asphalt	25'	No	Medium		8" Ductile	Local	3	1982	Structural Improvements	bb31'	\$ 1,044,000

City of Portland
 Ionia County, Michigan
 2007-2008 Street Inventory
 updated 9-29-2009
 Ranking Criteria: Priority - Top 20

Priority	Street Name	From	To	Length	Type	Width (ft)	Walks	Traffic Volume	Sanitary Condition	Water	ACT 51 Classification	PASER	Reconstructed	Action	Recommended Cross Section Fix or	Estimated Cost
13	Detroit St	Quarterline	Dead End	1836	Asphalt	31'	Yes	Medium		8" cast West to End; 6&8" Ductile West to Wine; 1 break near Bethel	Local	4	1991	Structural Improvements Required, water	bb31'	\$ 753,000
14	Bishop St	Looking Glass Ave	Dead End	476	Gravel	15'	No	Low	Poor	4"	Local	1		Total Reconstructing Required, water/sewer	bb 31'	\$ 267,000
15	N & S Virginia Ave	Kent	Kent	1421	Asphalt	31'	No	Low	Poor	6" Cast; 1 leak	Local	1	1982	Reconstruction, water/sewer	bb 31'	\$ 796,000
16	Vessey	Hill	Brush	381	Gravel	30'8"	No	Low		8" Ductile	Local	1		Requires Scraping Brine, Ready for Paving/Needs Sidewalks	bb 31'	\$ 114,000
17	W Looking Glass	North	Dead End	672	Gravel	12'	No				Local	1		Total Reconstruction	bb 31'	\$ 202,000
18	James St	Grand River	Charlotte Hwy	3060	Gravel	33'	Yes	Medium		4" & 8" Cast	Local	6 from GR - Grant/ 2 from Grant Newton St	1988	Continue Crack Sealing, water	bb 31'	\$ 918,000
19	Albro	Grand River	Detroit St	1280	Asphalt	N	Yes	Low		6'/1" Cast/Galv.; 3 breaks	Local	3	1984	Improvements	bb 31'	\$ 384,000
20	Storz Ave	Knox	Dead End	310	Asphalt	34'	Yes	Moderate		6" Cast; 2 breaks	Local	3	Barley to Knox 1984	Structural Improvements, water	bb 31'	\$ 127,000